



GOVERNMENT OF NEPAL
Rainas Municipality - Office of Municipality Executive
Tiniple, Lamjung, Gandaki Province, Nepal
BILL OF QUANTITIES (BOQ)

Name of Bidder / Firm : _____

IFB / Contract No. :RAINAS/NCB/W/083-84/02

S.N.	Description of Items	Unit	Quantity	Rate (NRs.)	Amount (NRs.)	Amount in Words	Remarks
A	Provisional Sum						
1	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party/insurance against damage to other persons and property.	P.S	1	1.00	70,000.00	Seventy Thousand Only	
2	Lab Test, PG commission	Nos	1	1.00	40,000.00	Forty Thousand Only	
B	Civil Construction Works						
1	Provide and installation of project information board of size 180 m X 1.2 m along with iron posts including excavation, concreting, backfilling etc all complete as per Dir Standard Specification for Road and Bridge Works	Nos	1.00				
2	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer.	Cum	812.65				
3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum	191.17				
4	Providing and laying of Plain Cement Concrete M 10 (or 1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications.(CRUSHED AGGREGATE)	Cum	21.95				
5	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC grade M15	Cum	42.30				
6	Providing and laying of Plain Cement Concrete (PCC) grade M20 in Foundation/sub-structure including formwork etc. all complete as per Drawing and Technical Specifications. CRUSHED AGGREGATE	Cum	336.10				

नेपाली
 कृष्ण कुमार
 सचिव (नवौतार)
 उप

7	Providing and laying, fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications	Kg	1,232.11				
C	Miscellaneous items						
1	Tubular GI Railing on Precast RCC Posts, 1.2 m High Above Ground Level Providing, fencing and erecting 50 mm dia painted GI pipe railing in 3 rows on precast M 20 grade RCC vertical posts 1.8 metres high (1.2 m above GL) with 3 holes 50 mm dia for pipe, fixed 2 metres center to, complete as per Drawing and Technical Specifications. Unit = meter (For 100 meter)	Rm	20				
	BOQ Total (Construction Works)						
	Provisional Sum (Ps)						
	VAT @ 13% (on BOQ Total)						
	Grand Total (BOQ Total + VAT + PS)						

Signature of Bidder: _____ Name: _____ Designation: _____

Name of Firm / Company: _____ Seal: _____ Date: _____

Email: _____



पूजा सतीश (महोदय)
महोदय